



भा.कृ.अ.प.-राष्ट्रीय उच्च सुरक्षा पशुरोग संस्थान
ICAR-National Institute of High Security Animal Diseases

(एवियन इन्फ्लूएंजा ओ.आई.ई. संदर्भ प्रयोगशाला)
(OIE Reference Laboratory for Avian Influenza)

आनंद नगर, भोपाल - ४६२०२२ (म.प्र.), भारत
Anand Nagar, Bhopal - 462022 (M.P.), India



EPABX Tel. No. 0755-2757542, 2750647, FAX: 0755-2758842, Website: www.nihsad.nic.in

F. No. 9-243/18-19/NIHSAD (P&S)

Dated: - 13.11.2018

To

.....

Sub:- Renovation of Work D & E+ Type Quarters (4 nos.) – reg.

Dear Sir(s),

Reputed firms/Authorized firms are invited for quoting their rates for following works as per under mentioned scope of work: -


Name of work	Qty.	Rate (In Rupees)	Total (In Rupees)
Renovation work in D & E+ Type Quarters (4 Nos.) + 1 No. (Annexure – I enclosed)	As per Scope of work		
GST@%			
Total FOR NIHSAD, Bhopal			

You are requested to please give Quotation/PI of the above said works. Please note that:-

1. Rates should be inclusive of all required materials and labour.
2. Rates are to be quoted on F.O.R. NIHSAD, Bhopal.
3. Awardee firm has to submit/deposit 10% of total value as Security money in shape of DD/FDR in favour of **ICAR Unit, NIHSAD, Bhopal** for the period of 14 months before undertaking the job.
4. Firms representative may visit at Institute premises during office hours before quoting the rates.
5. Warranty of work is to be offered for minimum 1 year.
6. Taxes, if any, to be shown separately.
7. E-Payment will be made within 30 days from the date of complete work in satisfactory condition.
8. Date & Time of Opening (Tentative): - **06.12.2018 at 11:30 AM.**
9. Completion Period: - 30 days.
10. Bid Validity: - 180 days.

The Quotation may be submitted upto **05.12.2018** in a closed envelope duly superscribed.

Yours Sincerely,


Adm. Officer

Annexure – I

Renovation of the kitchen and toilets of D type Quarter (4 in no.s), and E+ Type Quarter of ICAR-NIHSAD, Bhopal				
Sr. No.	Description of work	Qty.	Rate (In Rupees)	Total (In Rupees)
1.	<u>Flooring Work at Toilets (D Type and E+ quarter)</u> Providing and laying rectified Glazed Ceramic floor tiles of size 300 x 300mm or more (thickness to be specified by the manufacturer), of 1 st quality conforming to IS:15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, Laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc. complete.	80 m ²		
2.	<u>Flooring work a Kitchen (D Type and E+ Quarters)</u> Providing and laying polished vitrified floor tiles 600 x 600mm (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS: 15622 of approved make in all colours and shades, laid on cement based high polymer modified quick-set tile adhesive (Water based) conforming to IS: 15477, using 5kg. Adhesive per sqm of tile area, in average 6mm thickness. .	40 m ²		
3.	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 meters lead.	11 m ²		
4.	Marble work gang saw cut (polished and machine cut) of thickness 18mm for wall lining (veneer work), backing filled with a grout of average 12 mm thick in cement mortar 1:3 (1 cement: 3 coarse sand), including pointing with white cement mortar 1:2 (1 white cement : 2 marble dust) with an admixture of pigment to match the marble shade (To be secured to the backing by means of cramps , which shall be paid for separately). Udaipur green marble/Zebra green marble.	11 m ²		
5.	Mirror polishing on marble work/Granite work/stone work where ever required to give high gloss finish complete	11 m ²		
	GST @%			
	Total FOR NIHSAD, Bhopal			