



F. No. 9-131/21-22/NIHSAD (P&S)

Dated: - 06.12.2021

To

Sub:- Framed Chain Link Fencing around 750 KVA DG Set and other miscellaneous work related to CEA regulation 2010 at ICAR-NIHSAD, Bhopal – reg.

Dear Sirs,

Reputed firms/Authorized firms are invited for quoting their rates for the following work as per under mentioned scope of work:-

Description	Quantity	Amount
Framed Chain Link Fencing around 750 KVA DG Set and other miscellaneous work related to CEA regulation 2010	01 Job	
	<u>GST@...%</u>	
	Total	

Scope of work – Refer Annexure – I

Relevant & other terms & conditions are as below: -

1. Quotation should be submitted at the top Tender No F. No. 9-131/21-22/NIHSAD (P&S) “Framed Chain Link Fencing around 750 KVA DG Set and other miscellaneous work related to CEA regulation 2010 at ICAR-NIHSAD, Bhopal”. The last date of receipt of above quotation is 05.01.2022 Upto 5:00 PM. The Institute will not be responsible for any postal delays.
2. The rates should be quoted for F.O.R. ICAR-NIHSAD, Bhopal basis as per quotation based on the scope of work & quality of materials.
3. Discount, if any, should be indicated clearly.
4. This Institute is registered with the Department of Scientific & Industrial Research (DSIR), Govt. of India for purpose of availing custom duty exemption in terms of Government. Notification No. 51/96-Customs dt. 23.07.1996, amended by Notification No. 4312017 dated 30.6.2017, Notification No. 47/2017-Integrated Tax (Rate) dt. 14.11.2017 and Notfn. No.4512017- Central Tax (Rate) dt. 14.11.2017, Notfn. No. 45/2017- Union Territory Tax (Rate) dt. 14.11.2017. However, as per notification No. 45/2017-Central Tax (Rate) dated 14.11.2017 issued by the Min. of Finance, Scientific and Technical instruments, etc. are exempted from the Central tax (in excess of 2.5%) livable there on under section 9 of the Central Goods and Service Tax Act, 2017 supplied to the Departments & laboratories of the Central Government and State Governments, other than a hospital. Since, this Institute is a Scientific Research Institution under Indian Council of Agricultural Research, Min. of Agricultural Govt. of India, and also registered by Min. of Science and Technology, DSIR New Delhi vide their Registration Certificate No. TU/V/RG-CDE/1235/2019dated 01.09.2019.
5. GST should be indicated in clear terms separately. GSTIN Registration/TIN Number should be mentioned. As per the Govt. Notification No. 47/2017-Integrated Tax (Rate) dt. 14.11.2017 and Notfn. No.4512017- Central Tax (Rate) dt. 14.11.2017, Notfn. No. 45/2017- Union Territory Tax (Rate) dt. 14.11.2017. However, as per notification No. 45/2017-Central Tax (Rate) dated 14.11.2017.

Contd....2

6. The rates quoted should be valid for 180 days from the date of opening of quotation.
7. There should be no cutting/overwriting in the quoted rates.
8. Warranty – 01 year from the date of supply/completion of work.
9. Unattested/amended/overwritten figures will not be considered.
10. In all matters of disputes, the decision of the Director of this Institute shall be final and binding.
11. Maximum period of completion of work is 45 days.
12. TDS will be deducted from the bill as per applicable tax rules.
13. Payment terms: - Payment will be made reasonable time say within 30 days from the date of receipt of material in good condition without any damage and after installation of the equipment in accordance with the ordered specification at the end. **Since the mode of payment will be e-payment system, hence, Bank Account, Number, Name of Bank with location and IFSC code Number of Bank may be furnished on the body of the bill.**
14. Performance Security: within 20 (Twenty) days after the issue of a letter/PO by this Institute, the supplier, shall furnish performance security to the institute for an amount of 3% (of Total Ordered value) including the warranty obligation before undertaking the work.
15. The Institute reserves the right to reject any or all the quotation(s) received without assigning any reasons thereof.
16. Tentative date of opening of bid (06.01.2022 at 11:30 AM).

Encl: - Annexure - I

Yours sincerely,



(PS Sunil Kumar)
Administrative Officer
Phone No. 0755-2754672

Annexure – I

Scope of Work: - Framed Chain Link Fencing around 750 Kva DG Set and other miscellaneous work related to CEA regulation 2010 at ICAR-NIHSAD

SCHEDULE OF QUANTITIES

S.no.	Description of work	Unit	QTY	Rate (Rs.)	Amount (Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (All kind of soil)	Cum	5.00		
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum	2.50		
3	Brick work with fly ash lime bricks (FALG Bricks) conforming to IS:12894-2002, in super structure above plinth level up to floor two level in : Cement mortar 1:6 (1 cement : 6 sand)	cum	2.10		
4	20 mm cement plaster mix 1:4 (1 cement : 4 sand)	Sqm	18.00		
5	White washing with lime to give an even shade: New work (three or more coats)	Sqm	18.00		
6	Supplying at site Angle iron post & strut of required size (50X50X5 mm) including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. etc. complete	Kg.	280.0		
7	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	Sqm	50.0		
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Sqm	30.0		
9	Fabrication of Bucket stand made of M.S. Pipe 0.50 Meter Dia of size 2.40X1.00 Meter bucket hanging arrangement of 05 nos. 0.30 Meter Buckets. Fabrication of canopy of 18 SWG MS sheet for protecting it from rain.The base will be 0.6 meter wide including painting work.	No.	3.0		
10	All earthing pits must have a metal name plate and placed near earthing pits.	No.	32.0		
11	All equipment (VCB, AVAR Transformer, HT Panel, All Breaker and switches of LT Panel, DG Set etc.) of 33 KV electrical substation shall have marking and labelling on suitable position (Almost 70 nos.).	Job	1.00		
		Total Amount			
		GST @			
		Total Amount			